



ENTRANCE SECURITY DEVICES	
	ALL DOOR RELEASE SYSTEMS TO BE FAIR SAFE (U O.N.) AND BE TIED INTO THE BUILDING GLASS "E" SYSTEM.
I	EXISTING INTERCOM TO REMAIN
CR	EXISTING CARD READER TO REMAIN
DR	DOOR RELEASE BUTTON AT RECEPTION DESK TO REMAIN.
MAG	EXISTING MAGLOCK TO REMAIN.
MD	EXISTING MOTION DETECTOR TO REMAIN.
WAP	WIRELESS ACCESS POINT

T&E PLAN KEYED NOTES:
1 FLOOR OUTLETS SHOWN FOR LOADING PURPOSES ONLY.

SYMBOL	DESCRIPTION
 	INDICATES AREA OR ROOM NUMBER BASE BUILDING WALL & COLUMNS TO REMAIN
 	NEW WALL MOUNTED VOICE/DATA J-BOX WITH 1" DIA., STUB UP TO 6" ABOVE FINISH CEILING, PROVIDE BLANK COVER PLATE. NEW WALL MOUNTED VOICE J-BOX WITH 3/4" DIA., STUB UP TO 6" ABOVE FINISH CEILING FOR SINGLE WALL MOUNTED TELEPHONE.
 	NEW WALL MOUNTED ELECTRICAL DUPLEX OUTLET NEW WALL MOUNTED DUPLEX ELEC. OUTLET (GROUND FAULT INTERRUPTER) 44" A.F.F. U.O.N.
 	NEW WALL MOUNTED ELECTRICAL QUAD OUTLET - (1) REGULAR DUPLEX OUTLET AND (1) COMPUTER DUPLEX OUTLET-GRAY (MAX 3 DUPLEX ON CIRCUIT) INSULATED GROUND. NEW WALL MOUNTED 20 AMP SEPARATE CIRCUIT. SEE SCHEDULE, THIS SHEET.
 	NEW ELECTRICAL DEVICES LOCATE IN CONNECTOR ENCLOSURE KNOCK-OUT U.O.N., PROVIDE J-BOX & 1" DIA., STUB UP TO 6" ABOVE FINISH CEILING.
<u>FURNITURE OUTLETS</u> 	NEW FURNITURE MOUNTED ELECTRICAL DEVICES & ASSEMBLIES COORDINATE W/ FURNITURE DEALER AND CLIENT FOR ALL REQUIREMENTS. FURNITURE MOUNTED DUPLEX POWER OUTLET. FURNITURE MOUNTED 20 AMP SEPARATE CIRCUIT FURNITURE MOUNTED VOICE/DATA OUTLET.
<u>EXISTING OUTLETS</u> 	EXISTING DUPLEX OR QUAD OUTLETS TO REMAIN, G.C. TO CONFIRM ALL OUTLET ARE IN PROPER WORKING ORDER, NOTIFY ARCHITECT/ CLIENT FOR DISCREPANCIES. ALL EXISTING OUTLETS COVER PLATE TO MATCH NEW. EXISTING VOICE/DATA OUTLETS TO REMAIN
10.14.19	ISSUED TO THE ENGINEER
DATE	REVISIONS
PROJECT BOSNIAN HERZGOVENIA PM TO UN 211 EAST 43RD STREET New York, NY Partial 17TH FLOOR	
DRAWING TITLE ARCHITECTURAL ELECTRIC & VOICE/DATA PLAN	
SEAL & SIGNATURE	DATE
	PROJECT NUMBER
	WORKING DWG. BY
	DRAWING No.
10/14/2019 1576-1 AMH A-317.00 7 OF 9	
NYC DOB NUMBER (PLACE STICKER HERE)	